
CONSTRUCTION TECHNOLOGY AND MANAGEMENT



IIT GUWAHATI

TOPIC: COST ESTIMATION OF RESIDENTIAL BUILDING

Group Members:



Anurag: 210104020

Arnav: 210104021



Harsh Vardhan: 210104044

Akshat Aren: 210104012

Amit Kumar: 210104017



Plan of Ground Floor



Plan of First Floor



Shot on OnePlus
Powered by Quad Camera

Actual Site

Assumptions

1. Brickwork in superstructure above plinth level up to floor V with cement mortar 1:4 (1 cement: 4 coarse sand).
2. Providing and laying in position reinforced cement concrete with mix proportion 1:2:4 (1 cement: 2 coarse sand of zone III: 4 stone aggregate 20mm nominal size), excluding the cost of shuttering and reinforcement – work up to plinth level.
3. Consider 75% 20 mm and 25% 10 mm aggregates, sundries @2%, GST @18%, Contractor's profit and overhead @15%, and Cess @1%.
4. Standard size of brick as 190 x 90 x 90mm.
5. The thickness of boundary wall is 9 inches and the thickness of inner wall is 4.5inches.

Hierarchy of Construction Works

1. Earthwork in excavation for foundation
2. PCC Foundation
3. RCC Foundation
4. Backfilling
5. Columns
6. Plinth Beams
7. Flooring at ground floor
8. Beam at surface of first floor
9. Slab at level one
10. Beam at surface of second floor
11. Slab at level two
12. Brickworks
13. Plastering
14. Whitewashing
15. Painting
16. Tiling

1. Earthwork in Excavation for foundation



Volume Calculation:

1 Earthwork in Excavation								
Item no.	Description of Items	no.	length(feet)	Breadth(feet)	Height(feet)	Quantity(cubic feet)	Quantity in cum	
1	Earthwork in Excavation	18	6	6	5	3240	91.75	

Cost Calculation:

Item No.	Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3)	Rate(in rupees)	Total Amount(in rupees)
1	Excavation of Earth							
1.1	Labour	m3	91.74	Mate	714	42.84	3930.1416	
				Mazdoor	645	399.9	36686.826	
							40616.9676	40616.9676

2. PCC Foundation



Volume Calculation:

Item no.	Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum
			length(feet)	Breadth(feet)	Height(feet)		
2.1	PCC	18	5	5	0.75	337.5	9.56

Cost Calculation:

PCC Foundation							
2.1	Material						
	Cement	m3	0.0885				2787.75
	Sand	m3	0.177				567.108
	Coarse Aggregate	m3	0.354				2300
			0.6195				5654.858
							101787.444
2.2	Labour	0.6195	0.17	Mason	784	133.28	82.56696
		0.6195	1.83	Mazdoor	645	1180.4	731.226825
		0.6195	0.8	Bhisti	714	571.2	353.8584
		0.6195	0.07	Mixer Operator	784	54.88	33.99816
		0.6195	0.07	Mixer	800	56	34.692
		0.6195	0.07	Vibrator	350	24.5	15.17775
							1251.520095
							22527.36171

3. RCC Foundation



Volume Calculation:

Item no.	Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum
			length(feet)	Breadth(feet)	Height(feet)		
2.2	RCC work	1	1.25	0.83	1.25	1.296875	
		1	3	3	1.25	11.25	
		1	trapezoidal structure with depth= 0.75feet and cross section areas of upper surface= 9 sqfeet and lower surface= 25sqfeet				12.25
					Total volume	24.79	0.7

Cost Calculation:

Item No.	Item Description	Unit	Volume	Weight(kg)	Worker	Rate per day	Rate(per m3)	Rate(in rupees)	Total Amount(in rupees)
3	RCC Foundation								
	3.1 Material								
	Cement	m3	0.097					3055.5	
	Sand	m3	0.194					621.57	
	Coarse Aggregate	m3	0.388					2520.9	
	Steel	m3	0.0211	165.635 kg				10857.37	
								17055.34	306996.12
	3.2 Labour	0.702	0.17		Mason	784	133.28	93.56256	
		0.702	2		Mazdoor	645	1290	905.58	
		0.702	0.9		Bhisti	714	642.6	451.1052	
		0.702	0.07		Mixer Operator	784	54.88	38.52576	
		0.702	0.07		Mixer	800	56	39.312	
		0.702	0.07		Vibrator	350	24.5	17.199	
								1545.28452	27815.1214

4. Backfilling



Volume Calculation:

Backfilling					
Item no.	Description of Items	no.	Quantity(cubic feet)	Quantity in cum	Explanatory notes
1	Backfilling of foundation	18	2877.71	81.49	Total volume excavated-volume occupied by RCC work and lime concrete=> 3240-(24.79+337.5) cubic feet= 2877.71 cubic feet= 81.49 cum

Cost Calculation:

Item Description	Unit	Volume	Worker	Rate(per m3)	Rate(in rupees)	Total Amount(in rupees)
Backfilling						
Labour	m3	62.5	Machine	60 per m3	3750	3750

5. Columns



Volume Calculation:

Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum
		length(feet)	Breadth(feet)	Height(feet)		
Total columns above ground level	18	1.25	0.83	25	466.875	13.22

Cost Calculation:

Item Description	Unit	Volume	Worker	Rate(per m3)	Rate(in rupees)
Columns					
Material					
Cement	m3	1.84		57960	
Sand	m3	3.68		11790.72	
Coarse Aggregate	m3	7.365		27343.81	
Steel	m3	0.3305		170064.5	
				267159	
Labour					
	13.22	0.17	Mason	133.28	1761.9616
	13.22	2	Mazdoor	1290	17053.8
	13.22	0.9	Bhisti	642.6	8495.172
	13.22	0.07	Mixer Operator	54.88	725.5136
	13.22	0.07	Mixer	56	740.32
	13.22	0.07	Vibrator	24.5	323.89
					29100.6572
			Total Cost of Columns		296259.6672

6.Plinth Beams



Volume Calculation:

Item no.	Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum		
			length(feet)	Breadth(feet)	Height(feet)				
4.2	Plinth Beams								
4.2.1	Beams parallel to the length of the plot	3	9.625	0.83	1	23.96625	0.68		
		2	9.625	0.83	1	15.9775	0.45		
		3	10.25	0.83	1	25.5225	0.72		
		2	10	0.83	1	16.6	0.47		
		3	11.25	0.83	1	28.0125	0.79		
4.2.2	Beams parallel to the Breadth of the plot	2	6	0.83	1	9.96	0.28		
		2	11.7	0.83	1	19.422	0.55		
		2	4.33	0.83	1	7.1878	0.20		
		2	13.46	0.83	1	22.3436	0.63		
		2	7	0.83	1	11.62	0.33		
		2	10.96	0.83	1	18.1936	0.52		
Total Volume of Plinth Beams=							5.63 cum		

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Plinth Beams parallel to the length of the plot						
Material						
Cement	m3	0.433				13639.5
Sand	m3	0.866				2774.664
Coarse Aggregate	m3	1.732				6430.34444
Steel	m3	0.07775				40007.6
						62852.10844
Labour						
	3.11	0.17	Mason	784	133.28	414.5008
	3.11	2	Mazdoor	645	1290	4011.9
	3.11	0.9	Bhisti	714	642.6	1998.486
	3.11	0.07	Mixer Operator	784	54.88	170.6768
	3.11	0.07	Mixer	800	56	174.16
	3.11	0.07	Vibrator	350	24.5	76.195
						6845.9186

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Plinth Beams parallel to the Breadth of the plot						
Material						
Cement	m3	0.349			10993.5	
Sand	m3	0.699			2239.596	
Coarse Aggregate	m3	1.398			5190.31	
Steel	m3	0.06275			32289.09	
						50712.496
Labour						
	2.51	0.17	Mason	784	133.28	334.5328
	2.51	2	Mazdoor	645	1290	3237.9
	2.51	0.9	Bhisti	714	642.6	1612.926
	2.51	0.07	Mixer Operator	784	54.88	137.7488
	2.51	0.07	Mixer	800	56	140.56
	2.51	0.07	Vibrator	350	24.5	61.495
						5525.1626

7.Flooring



Volume Calculation

Flooring					
Item no.	Description of Items	Value	Explanatory notes		
5.1	Total plot area(sq. metres)	111.24	length of the plot= 59.5 feet and breadth of plot = 20.125 feet. Hence area = l*b = 1197.4375 sq. ft.= 111.24 sq. metres		
5.2	Surface area of plinth beams(top view) (sq. metres)	5.63			
5.3	Cross-section area of column(top view) sq. metres	1.74			
5.4	Surface area of flooring(sq.	103.87	111.24-(5.63+1.74) sq. metres		
5.5	volume of flooring				
5.5.1	Volume occupied by soil	26.38 cum	Height upto which soil is filled is 10 inches(0.254 meters) hence the volume= 103.87*(0.254)		
5.5.2	Volume occupied by PCC	5.28 cum	Height upto which PCC is done is 2 inches(0.0508 meters) hence the volume= 103.87*(0.0508)		

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per d	Rate(per m3) in rupees	Rate(in rupees)
Flooring						
Material						
Soil	m3	26.38				7914
Cement	m3	0.754				23751
Sand	m3	1.5				4806
Coarse Aggregate	m3	3.017				11201.12539
						47672.12539
Labour for pcc	5.28	0.17	Mason	784	133.28	703.7184
	5.28	1.83	Mazdoor	645	1180.35	6232.248
	5.28	0.8	Bhisti	714	571.2	3015.936
	5.28	0.07	Mixer Operator	784	54.88	289.7664
	5.28	0.07	Mixer	800	56	295.68
	5.28	0.07	Vibrator	350	24.5	129.36
						10666.7088
Labour for soil work	26.38	0.02	Mate	714	14.28	376.7064
	26.38	0.25	Mazdoor	645	161.25	4253.775
	26.38	0.02	Bhisti	714	14.28	376.7064
						5007.1878

8. Beam at surface of first floor

Volume Calculation

Beam at base of 1st floor							
			Dimensions				
Item no.	Description of Items	no.	length(feet)	Breadth(feet)	Height(feet)	Quantity(cubic feet)	Quantity in cum
7.1	Beams parallel to the length of the plot	3	9.625	0.83	1	23.97	0.68
		2	11	0.83	1	18.26	0.52
		3	10.25	0.83	1	25.52	0.72
		2	10	0.83	1	16.60	0.47
		3	14.67	0.83	1	36.53	1.03
7.2	Beams parallel to the Breadth of the plot	2	6	0.83	1	9.96	0.28
		2	11.7	0.83	1	19.422	0.55
		2	4.33	0.83	1	7.1878	0.20
		2	13.46	0.83	1	22.3436	0.63
		2	7	0.83	1	11.62	0.33
		2	10.96	0.83	1	18.1936	0.52
total volume= 5.93 cubic meters							

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Beams parallel to the length of the plot(1st floor)						
Cement	m3	0.476357			31500	15005.25
Sand	m3	0.952714			3204	3052.496571
Coarse Aggregate	m3	1.905429			3712.67	7074.227494
Steel	m3	0.0855			514567.29	43995.5033
						69127.47736
Labour	3.42	0.17	Mason	784	133.28	455.8176
	3.42	2	Mazdoor	645	1290	4411.8
	3.42	0.9	Bhisti	714	642.6	2197.692
	3.42	0.07	Mixer Operator	784	54.88	187.6896
	3.42	0.07	Mixer	800	56	191.52
	3.42	0.07	Vibrator	350	24.5	83.79
						7528.3092

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Beams parallel to the breadth of the plot(1st floor)				Total Volume	2.51	
Cement	m3	0.349714			31500	11016
Sand	m3	0.699429			3204	2240.969143
Coarse Aggregate	m3	1.398857			3712.67	5193.494949
Steel	m3	0.062			514567.29	31903.17198
						50353.63607
Labour	2.51	0.17	Mason	784	133.28	334.5328
	2.51	2	Mazdoor	645	1290	3237.9
	2.51	0.9	Bhisti	714	642.6	1612.926
	2.51	0.07	Mixer Operator	784	54.88	137.7488
	2.51	0.07	Mixer	800	56	140.56
	2.51	0.07	Vibrator	350	24.5	61.495
						5525.1626

9.Slab at level one



Volume Calculation

Slabbing								
			Dimensions					
Item no.	Description of	no.	length(feet)	Breadth(feet)	Height(feet)	Quantity(cubic f	Quantity in cum	Explanatory notes
8.1	total volume(S	1	63	20.125	0.5	633.94	17.95	
	volume occupied by beams at base of first							
8.2	floor(V)	1					5.93	
	volume occupied by columns at base of first							
8.3	floor(C)	18	1.25	0.83	0.5	9.375	0.265	
8.4	Extra Slabbing	1	7	3.5	0.5	12.25	0.35	
8.4 Total Volume for slabbing							15.07	S + E - (V/2) - C

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Slabbing			Total Volume	15.07		
Cement	m3	2.099036		31500	66119.63	
Sand	m3	4.198071		3204	13450.62	
Coarse Aggregate	m3	8.396143		3712.67	31172.11	
Steel	m3	0.37675		514567.29	193863.2	
						304605.5801
Labour	15.07	0.24	Mason	784	188.16	2835.5712
	15.07	2.5	Mazdoor	645	1612.5	24300.375
	15.07	0.9	Bhisti	714	642.6	9683.982
	15.07	0.07	Mixer Operator	784	54.88	827.0416
	15.07	0.07	Mixer	800	56	843.92
	15.07	0.07	Vibrator	350	24.5	369.215
						38860.1048

10.Beam at surface of second floor

Volume Calculation

Beam at surface of second floor						
Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum
		length(feet)	Breadth(feet)	Height(feet)		
Beams parallel to the length of the plot	3	9.625	0.83	1	23.97	0.68
	2	11	0.83	1	18.26	0.52
	3	10.25	0.83	1	25.52	0.72
	2	10	0.83	1	16.60	0.47
	3	14.67	0.83	1	36.53	1.03
Beams parallel to the Breadth of the plot	2	6	0.83	1	9.96	0.28
	2	11.7	0.83	1	19.422	0.55
	2	4.33	0.83	1	7.1878	0.20
	2	13.46	0.83	1	22.3436	0.63
	2	7	0.83	1	11.62	0.33
	2	10.96	0.83	1	18.1936	0.52
						total volume= 5.93 cubic meters

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Beams parallel to the length of the plot(2nd floor)						
Cement	m3	0.476357			31500	15005.25
Sand	m3	0.952714			3204	3052.496571
Coarse Aggregate	m3	1.905429			3712.67	7074.227494
Steel	m3	0.0855			514567.29	43995.5033
						69127.47736
Labour	3.42	0.17	Mason	784	133.28	455.8176
	3.42	2	Mazdoor	645	1290	4411.8
	3.42	0.9	Bhisti	714	642.6	2197.692
	3.42	0.07	Mixer Operator	784	54.88	187.6896
	3.42	0.07	Mixer	800	56	191.52
	3.42	0.07	Vibrator	350	24.5	83.79
						7528.3092

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Beams parallel to the breadth of the plot(2nd floor)				Total Volume	2.51	
Cement	m3	0.349714			31500	11016
Sand	m3	0.699429			3204	2240.969143
Coarse Aggregate	m3	1.398857			3712.67	5193.494949
Steel	m3	0.062			514567.29	31903.17198
						50353.63607
Labour	2.51	0.17	Mason	784	133.28	334.5328
	2.51	2	Mazdoor	645	1290	3237.9
	2.51	0.9	Bhisti	714	642.6	1612.926
	2.51	0.07	Mixer Operator	784	54.88	137.7488
	2.51	0.07	Mixer	800	56	140.56
	2.51	0.07	Vibrator	350	24.5	61.495
						5525.1626

11.Slab at level two (Roof)

Volume Calculation

Slabbing of roof							
Description of Items	no.	length(feet)	Breadth(feet)	Height(feet)	Quantity(cubic feet)	Quantity in cum	Explanatory notes
total volume(S)	1	63	20.125	0.5	633.94	17.95	
volume occupied by beams at base of first floor(V)	1					5.93	
volume occupied by columns at base of first floor(C)	18	1.25	0.83	0.5	9.375	0.265	
Total Volume for slabbing						14.72	S - (V/2) - C

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Roof Slabbing			Total Volume	14.72		
Cement	m3	2.050286			31500	64584
Sand	m3	4.100571			3204	13138.23086
Coarse Aggregate	m3	8.201143			3712.67	30448.13705
Steel	m3	0.368			514567.3	189360.7627
						297531.1306
Labour	14.72	0.24	Mason	784	188.16	2769.7152
	14.72	2.5	Mazdoor	645	1612.5	23736
	14.72	0.9	Bhisti	714	642.6	9459.072
	14.72	0.07	Mixer Operator	784	54.88	807.8336
	14.72	0.07	Mixer	800	56	824.32
	14.72	0.07	Vibrator	350	24.5	360.64
						37957.5808

12.Brickworks



Volume Calculation

Brickwork in superstructure(first floor)

Item no.	Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum
			length(feet)	Breadth(feet)	Height(feet)		
9.1	Boundary wall brickwc	1	6	0.75	11.5	51.75	1.47
			11.7			100.90	2.86
			10.96			94.53	2.68
			3.5			30.20	0.86
			9.625			166.03	4.70
		2	11			189.75	5.37
		2	10.25			176.81	5.01
		2	10			172.50	4.88
		2	11.25			194.06	5.50
		1	10.96			94.53	2.68
9.2	Internal wall brickwork	1	5.92	0.375	11.5	25.53	0.72
		1	11.8	0.375	11.5	50.89	1.44
		1	7.33	0.375	12	32.99	0.93
		1	7.25	0.375	11.5	31.27	0.89
		2	4.33	0.375	11.5	37.35	1.06
		2	13.49	0.375	11.5	116.35	3.29

		1	4	0.375	12	18.00	0.51
		1	6.92	0.375	11.5	29.84	0.85
		1	9.25	0.375	11.5	39.89	1.13
		1	11	0.375	11.5	47.44	1.34
		1	6.67	0.375	12	30.02	0.85
		1	9.5	0.375	11.5	40.97	1.16
		1	7	0.375	12	31.50	0.89
		1	10.5	0.375	11.5	45.28	1.28

9.3	Extra Brickwork	2	3.416	0.375	11.5	29.463	0.83
-----	-----------------	---	-------	-------	------	--------	------

9.4 Area acquired by door and window

Item	Type	No.	area per iter	total area(sq.ft)	Explanatory notes
Door	D3	5	17.5	87.5	
Door	D2	2	21	42	
Door	D1	2	24.5	49	
			total area	178.5	

			Volume occupied by doors= 1.9 cubic metres		volume= (total area*0.375) cubic feet= 1.9 cum
--	--	--	--	--	--

Item	Type	No.	area per item(sq.ft)	total area(sq.ft)	Explanatory notes		
Window	W1	2	22.5	45			
Window	W2	1	13.5	13.5			
			total area	58.5			
			Volume occupied by windows= 1.24 cubic metres		volume= (total area*0.75) cubic feet= 1.24 cum		
9.5 Final Brickwork excluding doors and windows							
6.4.1	total external brickwork(E) = 34.76	36 - 1.24					
6.4.2	total internal brickwork(I) = 15.28	17.18- 1.9					
	Total Volume= 50.04 cubic metres	E+I					

Brickwork in superstructure(ground floor)

Item no.	Description of Items	no.	Dimensions			Quantity(cubic feet)	Quantity in cum	
			length(feet)	Breadth(feet)	Height(feet)			
6.1	Boundary wall brickwork	1	6	0.75	11.5	51.75	1.47	
			11.7			100.90	2.86	
			10.96			94.53	2.68	
			3.5			30.20	0.86	
			2			9.625	166.03	4.70
			2			11	189.75	5.37
			2			10.25	176.81	5.01
			2			10	172.50	4.88
		2	11.25			194.06	5.50	
6.2	Internal wall brickwork	1	5.92	0.375	11.5	25.53	0.72	
		1	11.8	0.375	11.5	50.89	1.44	
		1	7.33	0.375	12	32.99	0.93	
		1	7.25	0.375	11.5	31.27	0.89	
		2	4.33	0.375	11.5	37.35	1.06	
		2	13.49	0.375	11.5	116.35	3.29	
		1	4	0.375	12	18.00	0.51	
		1	6.92	0.375	11.5	29.84	0.85	
							0.00	
		1	9.25	0.375	11.5	39.89	1.13	
		1	11	0.375	11.5	47.44	1.34	
		1	6.67	0.375	12	30.02	0.85	
		1	9.5	0.375	11.5	40.97	1.16	
		1	7	0.375	12	31.50	0.89	
		1	10.5	0.375	11.5	45.28	1.28	
							0.00	
6.3	Extra Brickwork						0.00	
		2	3.5	0.375	4	10.5	0.30	

6.4 Area acquired by door and window					
Item	Type	No.	area per item(sq.ft)	total area(sq.ft)	Explanatory notes
Door	D3	4	17.5	70	
Door	D2	2	21	42	
Door	D1	2	24.5	49	
			total area	161	
			Volume occupied by doors= 1.71 cubic metres		volume= (total area*0.375) cubic feet= 1.71 cum
Item	Type	No.	area per item(sq.ft)	total area(sq.ft)	Explanatory notes
Window	W1	1	22.5	22.5	
Window	W2	1	13.5	13.5	
			total area	36	
			Volume occupied by windows= 0.76 cubic metres		volume= (total area*0.75) cubic feet= 0.76 cum

Final Brickwork excluding doors and windows	
total external brickwork(E) = 32.55	33.31- 0.76
total internal brickwork(I) = 14.92	16.63- 1.71
Total Volume= 47.47 cubic metres	E+I

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Brickwork in superstructure			Total Volume	97.51		
Material						
Cement	m3	2.796			31500	88074
Sand	m3	11.184			3204	35833.5
brick	m3	83.58			6.5	353002
		Bricks Req.	54308			476909.5
Labour						
	97.51	0.25	Mason	784	196	19111.96
	97.51	0.4	Mazdoor	645	258	25157.58
	97.51	0.1	Bhisti	714	71.4	6962.214
						51231.754

13.Plastering



Area Calculation

Plastering			
Description	Value(sq. meters)	Explanation	thickness=0.02 m
Total area of brickwork(B)	651.76		
Total area of slab(S)	177.8		
total area of Plastering	1659.12	2*B + 2*S [the factor of 2 in brickwork is used for inner and outer plastering and the factor of 2 in slabs is used because there are 2 ceilings in the whole house]	

Cost Calculation

Item Description	Unit	Volume	Worker	Rate per day	Rate(per m3) in rupees	Rate(in rupees)
Plastering						
Material						
Cement	m3	6.63648			31500	209049.12
Sand	m3	26.54592			3204	85053.12768
						294102.2477
Labour						
	33.1824	0.6	Mason	784	470.4	15609.00096
	33.1824	0.1	Mazdoor	645	64.5	2140.2648
	33.1824	0.1	Bhisti	714	71.4	2369.22336
						20118.48912

1 4.Whitwashing



Area Calculation

whitewashing		
Total Area	1659.12 sq. meters	area for painting and whitewashing will be same as area of plastering

Cost Calculation

White Wash					
	Rate			Total Area	Total Cost
Total Cost	65			1659.12	107842.8

15.Painting



Area Calculation

Painting		
Total Area	1659.12 sq. meters	area for painting and whitewashing will be same as area of plastering

Cost Calculation

Painting					
	Rate			Total Area	Total Cost
	90			1659.12	149320.8

16.Tiling



Area Calculation

Tiling					
Tiling for Groundfloor					
Description	length(feet)	Breadth(feet)	Area(sq. feet)	Area in sq.meters	
Kitchen	11	6	66	6.13	
Bedroom 1	12.25	11	134.75	12.52	
Toilet 1	7.33	4.67	34.2311	3.18	
Toilet 2	5	6.67	33.35	3.10	
Dining Hall	11	11	121	11.24	
Bedroom 2	14	12	168	15.61	
Passage	4	4.41	17.64	1.64	
Toilet 3	7	4	28	2.60	
Tiling for 1st floor					
Description	length(feet)	Breadth(feet)			
Kitchen	11	6	66	6.13	
Bedroom 1	12.25	11	134.75	12.52	
Toilet 1	7.33	4.67	34.2311	3.18	
Toilet 2	5	6.67	33.35	3.10	
Dining Hall	11	11	121	11.24	
Bedroom 2	14	12	168	15.61	
Drawing Room	14.416	10	144.16	13.39	
Toilet 3	7	4	28	2.60	
Bedroom 3	13	11.5	149.5	13.89	
Balcony	3.416	11.5	39.284	3.65	
Total area for Tiling= 141.33 sq. meters					

Cost Calculation

Tiling					
	Rate			Total Area	Total Cost
	1076.39			141.33	152126.1987

Final Costing

Cost of Carpentry, Toilet, Electric Work , Plumbing
=15,79,992.33


Remaining Cost=29,20,007.67






























Total Cost =45,00,000























18% GST =8,10,000


15% Profit of Contractor=6,75,000

Total Cost(including GST and Profit)=59,85,000




ID		Task Mode	Name	Leveling Delay			March 2024								April 2024								May 2024					
					24	27	01	04	07	10	13	16	19	22	25	28	31	03	06	09	12	15	18	21	24	27	30	03
47			Shuttering	0 edays																								
48			RCC of slab	0 edays																								
49			RCC of bean	0 edays																								
50			Deshutterin	0 edays																								
51			Deshutterin	0 edays																								
52			Wall finishing	0 edays																								
53			Plastering	0 edays																								
54			Whitewashing	0 edays																								
55			Painting	0 edays																								
56			Finishing work	0 edays																								
57			Room Work	0 edays																								
58			Electric Wor	0 edays																								
59			Door	0 edays																								
60			Window	0 edays																								
61			Tiling	0 edays																								
62			Toilets	0 edays																								
63			Toilet water	0 edays																								
64			Sewage and	0 edays																								
65			Plumbing	0 edays																								
66			Toilet acces:	0 edays																								































Project: pPROJECT2 Date: Mon 01-04-24	Preleveled Task		Inactive Summary		Summary	
	Preleveled Split		Duration-only		Manual Summary	
	Task		Start-only		Project Summary	
	Manual Task		Finish-only		External Tasks	
	Split		Preleveled Milestone		External Milestone	
	Progress		Milestone		Deadline	
	Inactive Task		Delay			
	Inactive Milestone		Slack			
























































Project: pPROJECT2 Date: Mon 01-04-24	Preleveled Task		Inactive Summary		Summary	
	Preleveled Split		Duration-only		Manual Summary	
	Task		Start-only		Project Summary	
	Manual Task		Finish-only		External Tasks	
	Split		Preleveled Milestone		External Milestone	
	Progress		Milestone		Deadline	
	Inactive Task		Delay			
	Inactive Milestone		Slack			












































































Project: pPROJECT2 Date: Mon 01-04-24	Preleveled Task		Inactive Summary		Summary	
	Preleveled Split		Duration-only		Manual Summary	
	Task		Start-only		Project Summary	
	Manual Task		Finish-only		External Tasks	
	Split		Preleveled Milestone		External Milestone	
	Progress		Milestone		Deadline	
	Inactive Task		Delay			
	Inactive Milestone		Slack			


ID	1	Task Mode	Name	Leveling Delay	Duration	Start	Finish	Successors	03 Mar '24														10 M
									W	T	F	S	S	M	T	W	T	F	S	S			
1			House Construction	0 edays	169 days	Fri 01-03-24	Fri 16-08-24																
2			Foundation	0 edays	17 days	Fri 01-03-24	Sun 17-03-24	11															
3			Cleaning	0 edays	1 day	Fri 01-03-24	Fri 01-03-24	4FS-1 day															
4			Layout at Site	0 edays	1 day	Fri 01-03-24	Fri 01-03-24	5															
5			Excavation	0 edays	2 days	Sat 02-03-24	Sun 03-03-24	6															
6			PCC	0 edays	1 day	Mon 04-03-24	Mon 04-03-24	7															
7			Reinforcement	0 edays	5 days	Tue 05-03-24	Sat 09-03-24	8															
8			Shuttering	0 edays	2 days	Sun 10-03-24	Mon 11-03-24	9															
9			RCC	0 edays	2 days	Tue 12-03-24	Ved 13-03-24	10FS+3 days															
10			Deshuttering	0 edays	1 day	Sun 17-03-24	Sun 17-03-24	12															
11			Column upto plinth	0 edays	11 days	Mon 18-03-24	Thu 28-03-24	17															
12			Reinforcement	0 edays	2 days	Mon 18-03-24	Tue 19-03-24	13															
13			Shuttering	0 edays	2 days	Ved 20-03-24	Thu 21-03-24	14															
14			RCC	0 edays	2 days	Fri 22-03-24	Sat 23-03-24	15FS+3 days															
15			Deshuttering	0 edays	1 day	Ved 27-03-24	Ved 27-03-24	16															
16			Backfilling	0 edays	1 day	Thu 28-03-24	Thu 28-03-24																
17			Plinth Beams	0 edays	141 days	Fri 29-03-24	Fri 16-08-24																
18			Reinforcement	0 edays	4 days	Fri 29-03-24	Mon 01-04-24	19															
19			Shuttering	0 edays	3 days	Tue 02-04-24	Thu 04-04-24	20SS															
20			RCC	0 edays	3 days	Tue 02-04-24	Thu 04-04-24	21FS+3 days															
21			Deshuttering	0 edays	1 day	Mon 08-04-24	Mon 08-04-24	23															
22			Ground Floor Col	0 edays	18 days	Tue 09-04-24	Fri 26-04-24																
23			Reinforcement	0 edays	4 days	Tue 09-04-24	Fri 12-04-24	24															
24			Shutttering	0 edays	3 days	Sat 13-04-24	Mon 15-04-24	25SS															


Critical		Project Summary		Manual Summary Rollup	
Critical Split		Rolled Up Critical		Manual Summary	
Task		Rolled Up Critical Split		Start-only	
Split		Inactive Task		Finish-only	
Milestone		Inactive Milestone		External Tasks	
Slack		Inactive Summary		External Milestone	
Slippage		Manual Task		Deadline	
Summary		Duration-only		Progress	

ID		Task Mode	Name	Leveling Delay	Duration	Start	Finish	Successors	W	T	F	S	03 Mar '24				10 Mar '24			
	1												S	M	T	W	T	F	S	S
25			RCC	0 edays	3 days	Sat 13-04-24	Mon 15-04-24	26FS+3 days												
26			Deshuttering	0 edays	1 day	Fri 19-04-24	Fri 19-04-24	27												
27			Brickwork	0 edays	7 days	Sat 20-04-24	Fri 26-04-24	29												
28			Beam & Slab of g	0 edays	55 days	Sat 27-04-24	Thu 20-06-24													
29			Staging	0 edays	2 days	Sat 27-04-24	Sun 28-04-24	30												
30			Reinforcement	0 edays	4 days	Mon 29-04-24	Thu 02-05-24	31SS												
31			Reinforcement	0 edays	6 days	Mon 29-04-24	Sat 04-05-24	32												
32			Shuttering	0 edays	4 days	Sun 05-05-24	Ved 08-05-24	33SS,34SS												
33			RCC of slab	0 edays	5 days	Sun 05-05-24	Thu 09-05-24	36FS+3 days												
34			RCC of beam	0 edays	3 days	Sun 05-05-24	Tue 07-05-24	35FS+3 days												
35			Deshuttering c	0 edays	1 day	Sat 11-05-24	Sat 11-05-24													
36			Deshuttering c	0 edays	1 day	Mon 13-05-24	Mon 13-05-24	38												
37			Column and B	0 edays	18 days	Tue 14-05-24	Fri 31-05-24													
38			Reinforcement	0 edays	4 days	Tue 14-05-24	Fri 17-05-24	39												
39			Shuttering	0 edays	3 days	Sat 18-05-24	Mon 20-05-24	40SS												
40			RCC	0 edays	3 days	Sat 18-05-24	Mon 20-05-24	41FS+3 days												
41			Deshutterin	0 edays	1 day	Fri 24-05-24	Fri 24-05-24	42												
42			Brickwork	0 edays	7 days	Sat 25-05-24	Fri 31-05-24	44FS+1 day												
43			Beam and slab	0 edays	19 days	Sun 02-06-24	Thu 20-06-24													
44			Staging	0 edays	2 days	Sun 02-06-24	Mon 03-06-24	45,46												
45			Reinforcement	0 edays	4 days	Tue 04-06-24	Fri 07-06-24													
46			Reinforcement	0 edays	6 days	Tue 04-06-24	Sun 09-06-24	47												
47			Shuttering	0 edays	4 days	Mon 10-06-24	Thu 13-06-24	48SS,49SS												
48			RCC of slab	0 edays	5 days	Mon 10-06-24	Fri 14-06-24	51FS+3 days												

Critical		Project Summary		Manual Summary Rollup	
Critical Split		Rolled Up Critical		Manual Summary	
Task		Rolled Up Critical Split		Start-only	
Split		Inactive Task		Finish-only	
Milestone		Inactive Milestone		External Tasks	
Slack		Inactive Summary		External Milestone	
Slippage		Manual Task		Deadline	
Summary		Duration-only		Progress	


ID		Task Mode	Name	Leveling Delay	Duration	Start	Finish	Successors	W	T	F	S	03 Mar '24					10 M		
49			RCC of bean	0 edays	3 days	Mon 10-06-24	Wed 12-06-24	50FS+3 days					S	M	T	W	T	F	S	S
50			Deshutterin	0 edays	3 days	Sun 16-06-24	Tue 18-06-24													
51			Deshutterin	0 edays	3 days	Tue 18-06-24	Thu 20-06-24	58,59,60,61												
52			Wall finishing	0 edays	47 days	Mon 01-07-24	Fri 16-08-24													
53			Plastering	0 edays	16 days	Mon 01-07-24	Tue 16-07-24	54FS+2 days												
54			Whitewashing	0 edays	14 days	Fri 19-07-24	Thu 01-08-24	55FS+1 day												
55			Painting	0 edays	14 days	Sat 03-08-24	Fri 16-08-24													
56			Finishing work	0 edays	20 days	Fri 21-06-24	Wed 10-07-24													
57			Room Work	0 edays	10 days	Fri 21-06-24	Sun 30-06-24													
58			Electric Wor	0 edays	10 days	Fri 21-06-24	Sun 30-06-24	53,63,64,65,66												
59			Door	0 edays	4 days	Fri 21-06-24	Mon 24-06-24													
60			Window	0 edays	4 days	Fri 21-06-24	Mon 24-06-24													
61			Tiling	0 edays	8 days	Fri 21-06-24	Fri 28-06-24													
62			Toilets	0 edays	10 days	Mon 01-07-24	Wed 10-07-24													
63			Toilet water	0 edays	3 days	Mon 01-07-24	Wed 03-07-24													
64			Sewage and	0 edays	6 days	Mon 01-07-24	Sat 06-07-24													
65			Plumbing	0 edays	10 days	Mon 01-07-24	Wed 10-07-24													
66			Toilet acces	0 edays	5 days	Mon 01-07-24	Fri 05-07-24													
			Critical		Project Summary		Manual Summary Rollup													
			Critical Split		Rolled Up Critical		Manual Summary													
			Task		Rolled Up Critical Split		Start-only													
			Split		Inactive Task		Finish-only													
			Milestone		Inactive Milestone		External Tasks													
			Slack		Inactive Summary		External Milestone													
			Slippage		Manual Task		Deadline													
			Summary		Duration-only		Progress													





The Gantt chart template displays a timeline from April 21, 2024, to May 26, 2024. The timeline is divided into weekly segments, each labeled with the day of the week and the date. The legend below the chart defines the symbols and colors used for various project elements:


- Critical:** Solid red bar
- Critical Split:** Red dotted bar
- Task:** Solid blue bar
- Split:** Blue dotted bar
- Milestone:** Black diamond
- Slack:** Solid teal bar
- Slippage:** Solid olive bar
- Summary:** Grey bar with a black end cap
- Project Summary:** Grey bar with black caps at both ends
- Rolled Up Critical:** Solid red bar
- Rolled Up Critical Split:** Red dotted bar
- Inactive Task:** White bar with a black border
- Inactive Milestone:** Grey diamond
- Inactive Summary:** White bar with black caps at both ends
- Manual Summary Rollup:** Solid teal bar
- Manual Summary:** Black bar with caps at both ends
- Start-only:** Teal L-shaped bracket
- Finish-only:** Teal J-shaped bracket
- External Tasks:** Grey bar
- External Milestone:** Grey diamond
- Deadline:** Teal bar with a green downward arrow at the end
- Progress:** Solid blue bar




21 Apr '24							28 Apr '24							05 May '24							12 May '24							19 May '24							26 May '24				
S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W							
																																</							



	Critical	<div></div>	Project Summary	<div></div>	Manual Summary Rollup	<div></div>
	Critical Split	<div></div>	Rolled Up Critical	<div></div>	Manual Summary	<div></div>
	Task	<div></div>	Rolled Up Critical Split	<div></div>	Start-only	<div></div>
	Split	<div></div>	Inactive Task	<div></div>	Finish-only	<div></div>
	Milestone	<div></div>	Inactive Milestone	<div></div>	External Tasks	<div></div>
	Slack	<div></div>	Inactive Summary	<div></div>	External Milestone	<div></div>
	Slippage	<div></div>	Manual Task	<div></div>	Deadline	<div></div>
	Summary	<div></div>	Duration-only	<div></div>	Progress	<div></div>





[illegible]

	T	W	T	F	S	14 Jul '24					21 Jul '24					28 Jul '24					04 Aug '24					11 Aug '24											
	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S		
																																					97
																																					70

Critical

Critical Split

Task

Split

Milestone

Slack

Slippage

Summary

Project Summary

Rolled Up Critical

Rolled Up Critical Split

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

External Tasks

External Milestone

Deadline

Progress

